BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2024-25/OW/WORK_INDENT3939

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/07/2024-25, Date: 09-09-2024

Name of Work: Maintenance of Existing Borewells in ward no. 08 Amruthahalli Surrounding area.
(Job Code: 008-25-000001)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH	
				In Figures	In Words
1	70.00	The lifting of submergible pumpset from well.	Each	1543.95	Rupees One Thousand Five Hundred Forty Three and Ninety Five Paise Only
2	35.00	The Transportation of pumping machineries	Each	1235.16	Rupees One Thousand Two Hundred Thirty Five and Sixteen Paise Only
3	5.00	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months) Above 7.5 HP to up to 8.0 HP	Each	4136.76	Rupees Four Thousand One Hundred Thirty Six and Seventy Six Paise Only
4	5.00	For all types of submersible pumpsets above 10 HP and upto 11 H.P.	Each	5308.10	Rupees Five Thousand Three Hundred Eight and Ten Paise Only
5	10.00	For all types of submersible pumpsets above 12 HP and upto 13 H.P	Each	6158.30	Rupees Six Thousand One Hundred Fifty Eight and Thirty Paise Only
6	15.00	For all types of submersible pumpsets 15HP to 20 HP	Each	9191.65	Rupees Nine Thousand One Hundred Ninety One and Sixty Five Paise Only
7	25.00	Pump bowls of same type and make	No.	1543.95	Rupees One Thousand Five Hundred Forty Three and Ninety Five Paise Only
8	25.00	Intermediate Piece (I.P) With IP Leaded Bronxe bush	No.	1080.77	Rupees One Thousand Eighty and Seventy Seven Paise Only
9	35.00	Upper Flange	No.	669.05	Rupees Six Hundred Sixty Nine and Five Paise Only
10	35.00	lower Flange	No.	669.05	Rupees Six Hundred Sixty Nine and Five Paise Only
11	35.00	Upper/ Lower Housing	No.	1235.16	Rupees One Thousand Two Hundred Thirty Five and Sixteen Paise Only

U.Ramesh
Signature of the Contractor

Executive Engineer

Name of Work: Maintenance of Existing Borewells in ward no. 08 Amruthahalli Surrounding area.
(Job Code: 008-25-000001)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH	
				In Figures	In Words
12	35.00	Guide vane	No.	720.51	Rupees Seven Hundred Twenty and Fifty One Paise Only
13	35.00	Impeller Shell moulded with aluminium Bronze	No.	1543.95	Rupees One Thousand Five Hundred Forty Three and Ninety Five Paise Only
14	35.00	Discharge outlet (D.O) Bearing D.O Steel Bush	No.	2110.07	Rupees Two Thousand One Hundred Ten and Seven Paise Only
15	10.00	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages)	No.	1543.95	Rupees One Thousand Five Hundred Forty Three and Ninety Five Paise Only
16	20.00	Pump Coupling (Stainless Steel)	No.	1543.95	Rupees One Thousand Five Hundred Forty Three and Ninety Five Paise Only
17	40.00	Stud and Nuts	Each	205.86	Rupees Two Hundred Five and Eighty Six Paise Only
18	35.00	Motor Base With Pin	Each	514.65	Rupees Five Hundred Fourteen and Sixty Five Paise Only
19	20.00	The Starter of Motor up to 4 to 5 HP	No.	3602.55	Rupees Three Thousand Six Hundred Two and Fifty Five Paise Only
20	20.00	The Rotor of Motor up to 4 to 5 HP	No.	2058.60	Rupees Two Thousand Fifty Eight and Sixty Paise Only
21	35.00	Carbon Housing	No.	2058.60	Rupees Two Thousand Fifty Eight and Sixty Paise Only
22	35.00	The Carbon Housing (Thrust bearing block assembly complete with segment bearing pad).	No.	2264.46	Rupees Two Thousand Two Hundred Sixty Four and Forty Six Paise Only
23	30.00	Oil Seal	No.	360.26	Rupees Three Hundred Sixty and Twenty Six Paise Only
24	30.00	Oil Seal Steel Bush	No.	257.33	Rupees Two Hundred Fifty Seven and Thirty Three Paise Only

U. Ramesh

Signature of the Contractor

Executive Engineer

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಜ್ಞಾನಭಾರತಿ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Name of Work: Maintenance of Existing Borewells in ward no. 08 Amruthahalli Surrounding area.
(Job Code: 008-25-000001)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH	
				In Figures	In Words
25	35.00	Steel bearing Bush	No.	411.72	Rupees Four Hundred Eleven and Seventy Two Paise Only
26	40.00	Allen Screw	No.	1235.16	Rupees One Thousand Two Hundred Thirty Five and Sixteen Paise Only
27	35.00	Pump Key (Stainless Steel)	No.	669.05	Rupees Six Hundred Sixty Nine and Five Paise Only
28	10.00	Non return valve (NRV) assembly complete with rubber 'O' Ring	No.	669.05	Rupees Six Hundred Sixty Nine and Five Paise Only
29	25.00	Cable Guard	No.	360.26	Rupees Three Hundred Sixty and Twenty Six Paise Only
30	25.00	Strainer	No.	463.19	Rupees Four Hundred Sixty Three and Nineteen Paise Only
31	30.00	Brass Filter	No.	1080.77	Rupees One Thousand Eighty and Seventy Seven Paise Only
32	30.00	Lock Ring	Each	360.26	Rupees Three Hundred Sixty and Twenty Six Paise Only
33	30.00	The Carbon Housing (Top carbond / ferrodo padding)	Each	360.26	Rupees Three Hundred Sixty and Twenty Six Paise Only
34	35.00	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush	Each	874.91	Rupees Eight Hundred Seventy Four and Ninety One Paise Only
35	35.00	Circillps	Each	205.86	Rupees Two Hundred Five and Eighty Six Paise Only

U.Ramesh

Signature of the Contractor

Executive Engineer

Name of Work: Maintenance of Existing Borewells in ward no. 08 Amruthahalli Surrounding area.
(Job Code: 008-25-000001)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates o U RAMESH	
				In Figures	In Words
36	56.70	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m	Cum	296.64	Rupees Two Hundred Ninety Six and Sixty Four Paise Only
37	210.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete.75mm (weight of pipe -0.917 kg)	Mtr	233.24	Rupees Two Hundred Thirty Three and Twenty Four Paise Only
38	56.70	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	169.63	Rupees One Hundred Sixty Nine and Sixty Three Paise Only
39	600.00	Supply of Drinking Water through water tankers of Capacity 5000 Liters Hiring of Water Tanker. Hire Charges of Tractor 40 HP including Operator and Fuel. Procurement of Water. Providing causal labours (unskilled mazdoor heavy).	1	592.88	Rupees Five Hundred Ninety Two and Eighty Eight Paise Only

U. Ramesh
Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike